BANGALORE DIVISION.

Abstract Notification dated 30th November 1911.

The attention of the public is invited to the Notification dated 30th November 1911, calling for tenders for restoring the Bolappanhalli Tank, Closepet Sub-Taluk, published on pages 1419 and 1420, Part II of the *Mysore Gazette* dated 30th November 1911.

V. R. NIJAGAL,
Executive Engineer.

KOLAR DIVISION.

Dated 6th December 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 23rd December 1911, for restoring the Marlur tank, Registered No. 194, Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Marlur tank Registered No. 194, Goribidnur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work	*Per*	*Quantity*
Earthwork to bund with consolidation	C. yd.	10,659
Turfing	S. yd.	9,950
Stone patching	C. yd.	2,443
Gravel backing	"	1,628
Grade stone with index stones including chiselling and painting.	Each	46
B. M. Stones	"	2
Register number stone	"	1
Date stone	"	1
Gauge stone	"	1
Waste weir—		
Dismantling masonry	C. ft.	190
Brick in surki mortar	"	1,633
Slab stones	S. ft.	402
Repairing the existing rough stone apron	Lump sum.	
Rough stone work new	C. yd.	216
Surki plastering	L. S. Sqrs.	5·00
Jaggles over body wall	No.	37
Sluice—		
Earthwork cutting and refilling	C. yd.	349
Burnt brick in surki mortar	C. ft.	969
Burnt stone slabs with rough dressing	S. ft.	334
Plastering with cement	Sqr.	500
Gibbet stones	No.	2
Cutting orifice stones upper and lower	"	2
Plugs with rod, etc., chain	Lump sum.	
Dismantling old sluice and removing debris	"	

Dated 6th December 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to evening of 23rd December 1911, for constructing a 1st Class Police Station at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing a first class Police Station at Kolar," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

	Items of work	*Per*	*Quantity*
1	Earthwork excavating and filling basement ...	C. yd.	164
2	Concrete in chunam	C. ft.	882
3	Burnt stone in chunam	„	3,310
4	Burnt brick in chunam	„	3,624
5	Burnt stone slabs nicely dressed	Sq. ft.	327
6	Plastering with chunam	Sqr.	49·82
7	Whitewashing two coats	„	30·18
8	Colour-washing	„	19·64
9	Flooring with Cuddapah slabs over 3″ concrete and cement pointing	„	2·46
10	Flooring with hard-pressed clay tiles over 3″ concrete and cement pointing	„	6·27
11	Cut stone pillars including base and capital ($6\frac{1}{2}' \times 9'' \times 9''$) with nice dressing	Each	2
12	Teakwood work with wood-oiling	C. ft.	128·39
13	Do ornamental eaveboards with painting ...	R. ft.	170
14	Teakwood finials, large	Each	3
15	Do small	Each	6
16	Teakwood battened doors with hinges, etc., with iron clamps, etc., complete	S. ft.	132
17	Removing the existing battened iron bars doors from the existing Police Station with new iron clamps	Each	2
18	Teakwood battened windows with iron bars, glazed shutters, complete	Sq. ft.	72
19	Removing the existing ventilators of iron bars from the existing Police Station and fixing to new Police Station with new iron clamps	Each	2
20	Roofing with 1st Class Mangalore tiles over 1″ thick chunam and flat tiles with teak reepers, etc., complete	Sqr.	17·31
21	Mangalore ridge tiles set in mortar	R. ft.	55
22	Teakwood trusses with iron work, painting, etc., complete	L. S.	...
23	Painting doors and windows	Sqr.	5·23
24	Chunam pointing	„	2·70
25	Zinc sheet for valley	Sq. ft.	30
26	Wooden planking to portico	„	6
27	Sundry work such as removing and replacing racks for carbine, sword, etc., from the old building ...	L. S.	...
28	Clearing site and levelling ground	„	...

V. AIYASWAMI IYER,
Executive Engineer.